IRRIGATION DIVISION.

Dated 13th August 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Irrigation Division, up to 10th September 1918, for improving the channels from Hoskote large tank. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at High Ground, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the channels from Hoskote large tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Left channel.

1. Raising the lifting dam across the Kodihalla below left waste weir :—

Items of work	Per	Quantity	Rate Rs.	a.	p.	Cost Rs.	Total
Removing and relaying the heavy covering slabs in surki mortar ...	S. ft.	812					
Burnt brick in surki mortar	C. ft.	1,187					
Removing and refixing the beams and providing longer screw gearing rod to the shutter.	L. S.	Rs.					
Plastering with surki mortar	Sqr.	4·13					
Pointing with cement	"	8·04					
Earthwork to bank and other unforeseen works ...	L. S.	Rs.					

2. Providing wooden plugs and locking arrangements to sluices Nos. 4, 19, 20, 21 and 22 :—

Items of work	Per	Quantity	Rate Rs.	a.	p.	Cost Rs.	Total
One masonry sluice with 2 plug holes of 8" diameter	Each	1					
Two cast iron pipe sluices of 6" diameter	Do	2					
Two masonry sluices with plug holes of 9" diameter	Do	2					

3. Regrading channel bed :—

Items of work	Per	Quantity	Rate Rs.	a.	p.	Cost Rs.	Total
Removing and refixing bed grade stones to the required level	Each	158					
Preparing and fixing new bed grade stones to the required level ...	Do	51					
Regrading channel bed to the required level	L. S.	Rs.					

4. Constructing a scouring sluice in the 1st mile of the channel :—

Items of work	Per	Quantity	Rate Rs.	a.	p.	Cost Rs.	Total
Earthwork	C. yd.	70					
Concrete in surki mortar	C. ft.	132					
Burnt brick in surki mortar	"	644					
Burnt stone slabs roughly dressed	S. ft.	221					
Cut stone work	C. ft.	14					
Plastering with surki mortar	Sqr.	3·88					
Pointing with cement	"	·94					
Rough stone work dry	C. yd.	18					
Cutting apron and refilling bund including watering and tamping ...	L. S.	Rs.					
Teakwood shutter 2½×2½ with iron rod and frames and locking arrange-	"	"					

5. Constructing silt traps for small hullas entering the channel :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Constructing silt traps	Each	8					

6. Constructing a masonry relieving weir 45 ft. long at 3rd mile, 3rd furlong :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Earthwork excavating and forming bank	C. yd.	296					
Concrete in surki mortar	C. ft.	159					
Burnt brick in surki mortar	"	751					
Plastering with surki mortar	Sqr.	7·00					
Burnt stone slabs roughly dressed	S. ft.	185					
Rough stone work dry	C. yd.	204					
Date stone	Each	1					
Clearing site, turfing bank and baling water, etc.	L. S.	Rs.					

7. Constructing a super passage of 150 ft. long at 2—9 of the channel :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Earthwork excavation	C. yd.	1,189					
Concrete in surki mortar	C. ft.	908					
Burnt brick in surki mortar	"	4,794					
Burnt stone slabs roughly dressed	S. ft.	1,782					
Plastering with surki mortar	Sqr.	43·61					
Rough stone work dry	C. yd.	480					
Pointing with surki mortar	Sqr.	9·27					
Removing and relaying old slabs in surki mortar	S. ft.	227					
Old stone work with new jelly	C. yd.	100					
Baling water	L. S.	Rs.					
Temporary deviation of channel	"	"					
Turfing banks	"	"					
Preparing and fixing guard stones	Each	4					
Do date stone	"	1					
Do number stone	"	1					
Clearing site and lowering present body wall so as not to be above apron level.	L. S.	Rs.					

Right channel.

1. Providing wooden plugs and locking arrangements to sluices Nos. 17, 24, 25, 26, 28, 29, 30 and 31 :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Cast iron pipe sluice of 3" diameter	Each	1					
Two masonry sluices with plug holes of 9" diameter	"	2					
Cast iron pipe sluice of 4" diameter	"	1					
Two masonry sluices with plug holes of 6" diameter	"	2					
Cast iron pipe sluice of 6" diameter	"	1					
Masonry sluice with plug hole of 3" diameter	"	1					

2. Regrading channel bed :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Removing and refixing bed grade stones to the required level ...	Each	157					
Preparing and fixing new grade stones to the required level ...	"	16					
Regrading the channel bed to the required level	L. S.	Rs.					

3. Constructing a scouring sluice in the 1st mile of the channel :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs	a.	p.	Rs.	
Earthwork	C. yd.	70					
Concrete in surki mortar	C. ft.	133					
Burnt brick in surki mortar	"	644					
Burnt stone slabs roughly dressed	S. ft.	221					
Cut stone work	C. ft.	14					
Plastering with surki mortar	Sqr.	3·89					
Pointing with cement	"	·94					
Rough stone work dry	C. yd.	18					
Cutting apron and refilling bund including watering and tamping ...	L. S.	Rs.					
Teakwood shutter 2½×2½ with iron rod and frames and locking arrangements, etc., complete.	"	"					

4. Constructing silt traps for small hullas entering the channel :—

Items of work	Per	Quantity	Rate			Cost	Total
			Rs.	a.	p.	Rs.	
Constructing silt traps	Each	4					

S. A. RAMASWAMY IYER,
Executive Engineer.

WATER-SUPPLY DIVISION.

Abstract Notification dated 22nd July 1918.

Attention of the public is invited to the detailed notification calling for tenders for "Constructing protective works to No. 3 weir of Hessarghatta Tank," published in the *Mysore Gazette* No. 31, dated 1st August 1918, page 695.

M. K. NARASIMHA IYER,
For *Executive Engineer.*

KRISHNARAJASAGARA WORKS.

The attention of the public is invited to the notification published on the page 696 of Part IV of *Mysore Gazette*, dated 1st August 1918, regarding the public auction of one 40 H.P. Oil Engine in the premises of the General Stores at Krishnarajasagara.

B. B. GARUDACHARYA,
Superintending Engineer.

BANGALORE DIVISION.

Abstract Notification dated 29th July—1st August 1918.

Attention is invited to the notification calling for tenders for constructing an additional block adjacent to the District Office building at Bangalore, published in *Mysore Gazette*, dated the 8th August 1918.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette* dated 8th August 1918, calling for tenders for constructing an additional Laboratory for the Geological Department at Lambourne House in Bangalore.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 1st August 1918, Part IV, page 721, calling for tenders for restoring Ternahalli Cholaghattadakere Tank, Registered No. 479 of Kolar Taluk.

NOTICE.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 746, calling for tenders for restoring Ghatti-Madamangala Tank, Registered No. 602 of Bowringpet Taluk.